



# Infrastructure Review

Richard “RichiH” Hartmann - Sebastian Schubert

# Core Infra



- Cisco ASR 1006 for routing, ACLs, NAT64, DHCP
- Handful Cisco C3750 Switches
- 3 Arista 7050 Switches
- Two very old servers for all other Services
- Three additional servers for running Proxmox Cluster
  - running our video review and video live streaming management tools
- All Monitoring done via Prometheus, Loki, and Grafana
- Data for Public Dashboards sent and persisted to VM outside ULB

# Video


Capturing with our video boxes

See <https://github.com/FOSDEM/video> for details


Send streams to render farm

Send streams off-site for livestreaming and cutting into finished videos

Semi-automated review and cutting process via <https://github.com/yoe/sreview>



# Video Boxes




# First Version of the new Boxes




# Final Videobox



# Final Videobox.v2.docx




# Final Videobox.v2.docx



# Final Videobox.v2.docx



# Final Videobox.v2.docx



# Final Videobox.v2.docx


More details?











Check out the talk from Martijn and Angel

Happening right now



# Example Cabling for a room



<p><b>aw1120</b></p>     <p>cam: box93 sld: box86 vtp: voctop23</p>	<p><b>aw1126</b></p>     <p>cam: box46 sld: box95 vtp: voctop1</p>	<p><b>h1301</b></p>     <p>cam: box17 sld: box100 vtp: voctop2</p>	<p><b>h1302</b></p>     <p>cam: box59 sld: box84 vtp: voctop3</p>	<p><b>h1308</b></p>     <p>cam: box03 sld: box08 vtp: voctop4</p>	<p><b>h1309</b></p>     <p>cam: box37 sld: box54 vtp: voctop5</p>	<p><b>h2213</b></p>     <p>cam: box16 sld: box07 vtp: voctop6</p>	<p><b>h2214</b></p>     <p>cam: box05 sld: box14 vtp: voctop7</p>	<p><b>h2215</b></p>     <p>cam: box79 sld: box41 vtp: voctop8</p>	<p><b>janson</b></p>     <p>cam: box55 sld: box88 vtp: voctop9</p>	<p><b>k1105</b></p>     <p>cam: box67 sld: box48 vtp: voctop10</p>	<p><b>k3201</b></p>     <p>cam: box81 sld: box96 vtp: voctop11</p>
<p><b>k3401</b></p>     <p>cam: box65 sld: box98 vtp: voctop12</p>	<p><b>k3601</b></p>     <p>cam: box91 sld: box36 vtp: voctop30</p>	<p><b>k4201</b></p>     <p>cam: box99 sld: box38 vtp: voctop13</p>	<p><b>k4401</b></p>     <p>cam: box85 sld: box52 vtp: voctop14</p>	<p><b>k4601</b></p>     <p>cam: box69 sld: box10 vtp: voctop15</p>	<p><b>ua2114</b></p>     <p>cam: box45 sld: box44 vtp: voctop16</p>	<p><b>ua2118</b></p>     <p>cam: box47 sld: box62 vtp: voctop17</p>	<p><b>ua2220</b></p>     <p>cam: box39 sld: box12 vtp: voctop18</p>	<p><b>ub2147</b></p>     <p>cam: box43 sld: box80 vtp: voctop19</p>	<p><b>ub2252a</b></p>     <p>cam: box63 sld: box58 vtp: voctop20</p>	<p><b>ub4132</b></p>     <p>cam: box51 sld: box40 vtp: voctop21</p>	<p><b>ub4136</b></p>     <p>cam: box87 sld: box34 vtp: voctop29</p>
			<p><b>ub5132</b></p>  	<p><b>ub5230</b></p>  	<p><b>ud2120</b></p>  	<p><b>ud2208</b></p>  	<p><b>ud2218a</b></p>  	<p><b>ud6215</b></p>  			



**Room ub2252a**

Room Status:

side-by-side presenter	side-by-side slides
fullscreen presenter	fullscreen slides

Mixer on [box58.video.fosdem.org](https://box58.video.fosdem.org); [Grafana](#)

**Inputs (pre-fader)**

IN1

🎧 L

🎧 R

IN2

🎧 L

🎧 R

IN3

🎧 L

🎧 R

**Outputs (post-fader)**

L

R

**Stream**

**Camera**



**Slides**





**Audio**




Cambox [box63.video.fosdem.org](https://box63.video.fosdem.org)

Slidesbox [box58.video.fosdem.org](https://box58.video.fosdem.org)


# Render Farm 2023 Edition



# Render Farm 2024-2025 Edition



# Timelines



## Installation of router

2016: Friday  
2017: December  
2018: December  
2019: December  
2020: December  
2023: January  
2024: January 24th (new 10g uplink)  
2025: January 6th

## Network up and Running

2015: Saturday 5:00  
2016: Friday 19:00  
2017: Friday 17:00  
2018: Friday 12:00  
2019: Thursday, last hiccups fixed Fri. 19:00  
2020: Friday 18:00  
2023: Friday 20:20  
2024: Friday ~14:30  
2025: Wednesday 16:00, last hiccups fixed Fri 12:20

# Timelines

## Monitoring

2016: Saturday 12:00

2017: Saturday 09:00

2018: January

2019: January

2020: January (2019!)

2023: January 13th , kept it running ...

2024: Immediate ;)

2025: Jan 13th, 2023 ;)

## Video

2016: Saturday 11:30

2017: Saturday 09:30

2018: Saturday 08:30


2019: Friday 21:00

2020: Friday 19:00

2023: Friday ~22:00

2024: Friday 23:00

2025: Friday 20:30



# Redoing our setup for 202(4|5)


Plan was made to replace the old servers with a cluster onsite

Migration away from the servers still ongoing, first VMs running and giving you DNS64 and providing monitoring

With the new cluster we also needed more bandwidth for Software Defined Storage


Replaced the old stacked switches with 2 “new” switches (Builddate: 2012-07-25) that now do MLAG - got rid of Spanning tree in the setup

.... still migrating workloads to the new cluster



# Uplinks

# colt



# dstny

# Clone our Conference

- Clone our Infrastructure: <https://github.com/FOSDEM/infrastructure>
- Check out our video setup: <https://github.com/FOSDEM/video/>



Q & A

